

Vetro

INSTALLATION SITE PREPARATION CHECKLIST

GAGGIA MILANO

Model	STANDARD Version		TALL Version	
	☐ 2-Group	☐ 3-Group	☐ 2-Group	☐ 3-Group
Dimensions (WxHxD)	28.7" x 18.5" x 20.9"	35.4" x 18.5" x 20.9"	28.7" x 20.5" x 20.9"	35.4" x 20.5" x 20.9"
Weight	100 lb	137 lb	100 lb	137 lb
Power Cord Plug	NEMA 6-20P	NEMA 6-30P	NEMA 6-20P	NEMA 6-30P
Max Absorbed Power	3700 W	4800 W	3700 W	4800 W
Voltage & Frequency	220 V / 60 Hz			

GENERAL MACHINE ENVIRONMENT


- ☐ The installation area is clean and clear of dust and tools. It is not located in an active construction zone.
- ☐ The counter accommodates the machine size and weight (refer to model table).
- ☐ An access hole has been pre-drilled in the counter for drainage and power in accordance with model installation template.
- ☐ Hole in counter is fitted with a collar to protect electrical cord, water line & drain tube.
- ☐ Machine can safely be installed with a minimum clearance of 3" from the back wall, 4" on each side and 12" on top.

ELECTRICAL REQUIREMENTS

- ☐ Power outlet receptacle is: NEMA 6-20R (**2-Group** models) or NEMA 6-30R (**3-Group** models).
- ☐ Dedicated electrical circuit meets the Vetro model power requirements.
- ☐ No extension cord or power strip on the circuit.

2-GROUP MODELS

NEMA 6-20



3-GROUP MODELS

NEMA 6-30



Legend

Ground

Hot/Line

WATER REQUIREMENTS

Pressure & Hardness

- ☐ Pressure is between 44 PSI & 116.03 PSI.
- ☐ pH range is between 6.5 and 7.5.
- ☐ Hardness (TDS) is between 89 PPM and 142 PPM.

MANDATORY – Machine water line must be equipped with a water filtration system with softness/filtration capabilities and a descaling device.



Water Network

- ☐ The water network provides cold, drinkable tap water.
- ☐ Dedicated 3/8" diameter water line.
- ☐ Shutoff valve with a 3/8" G male pipe fitting on machine's end.

HIGHLY RECOMMENDED – Connection to a floor drain in accordance with local health code.